

DATE	QUESTION	ANSWER
4.4.2019	1. CAG-HPPL-ILF-LTOT01-NAK-MAN-920-001 Rev001: Scope of work for General Contractor – LOT 1 - According to §9.3 Design works delivered by the Employer or Third Parties, "on General Contractor's request, the Employer will provide available as-built documentation of existing facilities influenced by the Project, further internal guidelines, procedures and specifications" Bidder respectfully Employer to provide these documents as complements to ITT documents, in particular for those LV5 / S5 included in the scope of work.	1. The list of internal standards includes the following work for General Contractor – LOT 1. Design works delivered by the Employer or Third Parties, "on General Contractor's request, the Employer will provide available as-built documentation of existing facilities influenced by the Project, further internal guidelines, procedures and specifications" Bidder respectfully Employer to provide these documents as complements to ITT documents.
	2. CAG-HPPL-ILF-LTOT02-NAK-MAN-920-001 Rev001: Scope of work for general contractor - lot II - According to §9.3 Design works delivered by the Employer or Third Parties, "on General Contractor's request, the Employer will provide available as-built documentation of existing facilities influenced by the Project, further internal guidelines, procedures and specifications" Bidder respectfully Employer to provide these documents as complements to ITT documents.	2. The list of internal standards includes the following N4G standards will be handed over EPC on kick-off meeting, as well as as-built of existing LV's.
	3. CAG-HPPL-ILF-GENER-LIN-SPC-803 Rev000 Pressure Tests and Stress tests - Specification - Article 3.2.3, the specification states that "According to TPG 702 04, the length of each individual tested section should not be more than 15 km and the internal volume should not be more than 6000 m3. "With 6000m3, the estimated length of each test section will be 4000m long. Please confirm the requirement of 6000m3 for internal volume?	3. The design must respect the technical standards of CR, in case that the individual tested section is longer or the volume is higher than stated in TPG 702 04, it is necessary to acquire positive consent of the future operator and subsequently the approval of Technical inspection of the Czech republic (TČR).
	4. CAG-HPPL-ILF-GENER-LIN-SPC-803 Rev000 Pressure Tests and Stress tests - Specification - From article 3.3, Tenderer understands that minimum pressure testing is 101.03 bar for 50"x18mm, coefficient 1.21 with design pressure. Please confirm pressure testing for 50"x18.5mm?	4. The test pressures for both stressed tested pipeline categories (A and B) shall be calculated on the base of formula stated in the chapter 3.3 of related specification "CAG-HPPL-ILF-GENER-LIN-SPC-803 Rev 000 Pressure Tests and Stress tests Specification" with respect to the actual line pipes delivery, actual yield point and actual condition of the construction.  We don't understand the small discrepancy in the value of test pressure, according to the calculation in above mentioned specification, the value of minimum test pressure for pipe 50"x18 mm is 104.4 barg and not 101.03 barg.  Calculation of test pressures for pipeline in category B (50"x21.5 mm) shall be executed analogically with calculation for pipeline in category A (50" x 18 mm).
	5. Invitation to submit indicative tender bids in negotiated procedure with prior publication - Bidder would appreciate an explanation of clause 5.6, and particularly the end of the sentence "or otherwise the Contracting Entity shall inform the Bidder that their indicative Tender Offer was delivered after the Indicative Tender Offer Submission Deadline". Is it possible to submit the indicative tender offer after the 25/04/19?	5. No, deadline for submission of Indicative Tender Offers is April 25, 2019, 2:00 p.m. unless otherwise the Contracting Entity will not extend the deadline.
	6. Tender Documentation, clause 11.2.2 - In clause 11.2.2, the Contractor's Project Execution Plan shall consider the 10 months scenario. In instruction 7, the EPSC shall consider the 14 months scenario. Tenderer would appreciate to issue a Project Execution Plan consistent with the schedule of rates.	6. Contracting Entity require to submit Project Execution Plan - 10 months scenario according to clause 11.2.2 of the Tender Documentation to verify the Bidder's efficiency and capability to execute works in such period. SPQ shall be provided for all requested scenarios.
	7. EIA - In article 5.4.2, Clearing of General Technical Requirements, CAG-HPPL-ILF-GENER-GEN-MAN-800, Bidder has to consider requirements of the EIA. Please communicate EIA and specific requirements.	7. EIA including specific requirements is an official and binding document and is available as a public document under the following address: <a href="https://portal.cer.cz/eia/ia/detail/EIA_M2P477">https://portal.cer.cz/eia/ia/detail/EIA_M2P477</a>
	8. Tender Documentation, clause 11.2 Evaluation Criteria - Bidder understood that one lot only can be awarded. However, in article 11.2.8 and 11.2.9, Contracting Entity is offering the possibility to offer a lump sum price for one "Lot" or for both Lots" for 10 and 11 months scenarios. Please clarify the mechanism for both Lots award?	Bidder may submit the tender offer for both Lots, however one Bidder may be awarded in one Lot only - please see point 11.1 third paragraph (bold). Point 11.2.1 is same for both lots - does not matter if there is "Lot" or "Lot" or for both Lots".
5.4.2019	1. Reference document: CAG-HPPL-ILF-LTOT01-NAK-MAN-920-001 "Scope of Work for General Contractor – LOT I". Section 9.2 "Other Works Provided by Third Parties" (if NOT works (NOT))  Reference document: CAG-HPPL-ILF-LTOT02-NAK-MAN-920-001 "Scope of Work for General Contractor – LOT II". Section 9.2 "Other Works Provided by Third Parties" (if NOT works (NOT))  CONTRACTOR asks confirmations that EMPLOYER will provide NOT service/works even during CONTRACTOR WPQR trials and testing, welders and welding operators trials and performance qualification.	1. EMPLOYER provides NOT service/works in case of welders - pre-production testing on site. WPQR trials and testing as well as the welders' operators' certification trials incl. NOT are in CONTRACTOR's responsibility
5.4.2019	1. Reference document: CAG-HPPL-ILF-LTOT01-NAK-MAN-920-001 "Scope of Work for General Contractor – LOT I". Section 9.2 "Other Works Provided by Third Parties" (if NOT works (NOT)) Reference document: CAG-HPPL-ILF-LTOT02-NAK-MAN-920-001 "Scope of Work for General Contractor – LOT II". Section 9.2 "Other Works Provided by Third Parties" (if NOT works (NOT)) CONTRACTOR asks confirmations that EMPLOYER will provide NOT service/works even during CONTRACTOR WPQR trials and testing, welders and welding operators trials and performance qualification.	1. EMPLOYER provides NOT service/works in case of welders - pre-production testing on site. WPQR trials and testing as well as the welders' operators' certification trials incl. NOT are in CONTRACTOR's responsibility
	2. Within folder "Annex 1 / 3. Employer Requirements", following documents are available only in Czech: CAG-HPPL-ILF-GENER-BO2-MAN-900-000 Spill and Flood Protection Plan CAG-HPPL-ILF-GENER-BO2-MAN-901-000 Emergency plan CAG-HPPL-ILF-GENER-BO2-T2P-902-000 Fire Safety - Report CAG-HPPL-ILF-GENER-BO2-T2P-902-001 HSE Plan for Construction Phase Can you please provide them in English?	2. Unfortunately documents are available only in Czech.